


NOTES:

1. CONCRETE: 4,000 PSI @ 28 DAYS. CEMENT TO BE PER ASTM C-150.
2. EACH PRECAST CONCRETE DECK POST FOOTING WEIGHS 115# (.03CY)

ITEM NO: 240300

updated: 12/13/10

DWG. NO. S1	Prepared for: <i>Michie Corporation</i>	Project Name Project Location		 MICHE CORPORATION, INC. 173 BUXTON INDUSTRIAL DRIVE-PO BOX 870 HENNIKER, NH 03242 PHONE: 603-428-3218 FAX: 603-428-7426	
	14"x14" Precast Concrete Deck Post Footing		Scale: AS SHOWN		
Project No. XXXX		Date: 1/8/2013	Designed by:	Drawn by: PDH	Checked by: XXX