



NOTES:

1. CONCRETE: 4,000 PSI MINIMUM @ 28 DAYS, PER ASTM C-478 (6.1). CEMENT TO BE PER ASTM C-150.
2. BUTYL RUBBER JOINT SEALANT PER ASTM C-990 & AASHTO M-198.
3. BITUMINOUS ASPHALT COATING (IF REQUIRED) TO BE SHOP APPLIED.

MORTAR BY CONTRACTOR		B1
BUTYL RUBBER JOINT SEALANT		B2
MORTAR PIPE CONNECTION		C1
FLEXIBLE SLEEVE PIPE CONNECTION		C2
COMPRESSION GASKET		C3
ASPHALTIC COATING		D

Revised: 7/22/14

DWG NO.
S1

Customer:

Project Name:
Project Location:

2' DIAMETER DROP INLET

Project No:

Scale: AS SHOWN

Date:

Designed by:

Drawn by: PIL

Checked by: XXX



173 BUXTON INDUSTRIAL DRIVE-PO BOX 870
HENRIKER, NH 03242
PHONE: 603-428-3218
FAX: 603-428-7426
www.michiecorp.com